

## **Release Notes for DrayTek Vigor 120 v2 (UK/Ireland)**

Firmware Version	3.7.2 (Formal Release)
Release Type	<b>Regular</b> – Upgrade recommended when convenient
Build Date	24 <sup>th</sup> May 2018
Release Date	31 <sup>st</sup> May 2018
Revision	74089
Applicable Models	Vigor 120 v2
ADSL Modem Code	332201 Annex A
Locale	UK & Ireland Only

### **New Features**

(None)

### **Improvement**

1. This firmware includes improvements to harden the web interface against attacks

### **Known Issues**

(None)

---

### **Important Note**

This firmware is for the Vigor 120 v2. For the Vigor 120 v1 please see the website.

For more UK product details & specification, please visit <http://www.draytek.co.uk>

See <http://www.draytek.co.uk/support/product-knowledgebase> for Vigor 120 setup examples.

### **NOTE: ADSL Modem Codes**

- For general purpose usage on UK lines, modem code 332201 is recommended.
- For ADSL2+ Annex M lines, the latest modem code 3471101 is suggested.
- For line speeds of less than 4Mbps, on lower quality lines a modem code with more conservative parameters, 310811 is suggested


### **Firmware File Types**

The ZIP file contains the firmware with two different file extensions, .ALL and .RST. The firmware is identical but the RST file contains factory default settings. If you install the ALL file, your modem will retain all existing settings. If you use the RST file, all settings will be wiped from your modem.

## **Upgrade Instructions**

It is recommended that you take a configuration backup prior to upgrading the firmware. This can be done from the modem's system maintenance menu.

To upgrade firmware, select '*firmware upgrade*' from the modem's system maintenance menu and select the correct file. Ensure that you select the ALL file unless you want to wipe out your modem's settings back to factory default.



## **Manual Upgrade**

If you cannot access the modem's menu, you can put the modem into 'TFTP' mode by holding the RESET whilst turning the unit on and then use the Firmware Utility. That will enable TFTP mode. TFTP mode is indicated by all LEDs flashing. This mode will also be automatically enabled by the modem if there is a firmware/settings abnormality. Upgrading from the web interface is easier and recommended – this manual mode is only needed if the web interface is inaccessible.

---

Firmware Version	3.2.8.2 (Formal Release)
Release Type	<b>Regular</b> – Upgrade recommended when convenient Note: A previous firmware (3.2.8.1) was a <b>critical release</b> . This f/w includes all changes/improvements that were in 3.2.8.1.
Build Date	10 <sup>th</sup> April 2017
Release Date	24 <sup>th</sup> April 2017
Revision	63056
Applicable Models	Vigor 120 v2
ADSL Modem Code	332201 Annex A
Locale	UK & Ireland Only

### **New Features**

(None)

### **Improvement**

1. Resolved Web UI display issue

### **Known Issues**

(None)

Firmware Version	3.2.8.1 (Formal Release)
Release Type	<b>Critical</b> – Upgrade recommended immediately
Build Date	7 <sup>th</sup> February 2017
Release Date	31 <sup>st</sup> March 2017
Revision	62309
Applicable Models	Vigor 120 v2
ADSL Modem Code	332201 Annex A
Locale	UK & Ireland Only

### **New Features**

(None)

### **Improvement**

1. Security improvements including one or more considered critical.

### **Known Issues**

1. Web UI menu has cosmetic display issue which will be corrected in the next firmware release

Firmware Version	3.2.8
Firmware Build	6th July 2015
Applicable Models	Vigor120 v2
ADSL Firmware	332201 Annex A
Locale	UK ONLY

### **New Features**

1. Supports automatic reboot after a specified number of hours with the "sys autoreboot" telnet command

### **Improvement**

(None)

Firmware Version	3.2.7
Firmware Build	6th February 2015
Applicable Models	Vigor120 v2
ADSL Firmware	332201 Annex A
Locale	UK ONLY

### **New Features**

1. Support for ADSL Status reporting via WAN2 on routers that support it (currently Vigor 2860 3.7.8 & Vigor 2925 3.7.8.1).

### **Improvement**

1. PPPoE server improvements for greater interoperability with more PPPoE clients

Firmware Version	3.2.6
Firmware Build	24th May 2011
Applicable Models	Vigor120 v2
ADSL Firmware	232201 Annex A
Locale	UK ONLY

### **New Features**

(None)

### **Improvement**

1. Minor region specific changes

Firmware Version	3.2.4.4
Firmware Build	27th July 2010
Applicable Models	Vigor120 v2
ADSL Firmware	232201 Annex A
Locale	UK ONLY

### **New Features**

(None)

### **Improvement**

1. Corrected: ADSL TX throughput can not exceed 1Mbps while ADSL link is on Annex M mode.
2. Improved: ADSL link problem.
3. Fixed PPPoE passthrough issue could cause some traffic not to be passed (ichat, 2nd life)



Firmware Version	3.2.4
Firmware Build	4th November 2009
Applicable Models	Vigor120 v2
ADSL Firmware	232201 Annex A
Locale	UK ONLY

### **New Features**

(None)

### **Improvement**

1. Improved: Some DSL interoperability problems occurred after updating DSL API driver.
2. Corrected: "G.Lite" item on WUI for annex A is lost.

**First Firmware Release for this model**

**[END OF FILE]**

