

## **Release Notes for DrayTek VigorAP 1062c (UK/Ireland)**

Firmware Version	5.0.2 (Formal Release)
Release Type	<b>Regular</b> – Upgrade recommended when convenient
Release Date	3 <sup>rd</sup> October 2024
Build Date	26 <sup>th</sup> August 2024
Web Version	r3662.244b7698
Core Version	r638
Applicable Models	VigorAP 1062c
Locale	UK Only

### **New Features**

(None)

### **Improvements**

1. The reset button can be optionally enabled/disabled
2. Fix for the compatibility with VigorACS platform
3. The TR-069 username and password allowed characters note added:

Username

a-z,A-Z,0-9,@.-%

Password

a-z,A-Z,0-9,-%!\$/()=?\*

### **Known Issues**

(None)

---

## Firmware File Types


The file name of the firmware controls which upgrade type is performed.

If the file name is unchanged (e.g. **xxxx.sfw**) then the upgrade will just upgrade the firmware, whereas renaming the firmware to a **.rst** extension will wipe all settings back to factory defaults when upgrading the firmware.

## Upgrade Instructions

It is recommended that you take a configuration backup prior to upgrading the firmware. This can be done from the AP's system maintenance menu.

To upgrade firmware, select '*firmware upgrade*' from the AP's system maintenance menu and select the correct file. The access point will perform the upgrade and automatically reboot once this completes.



## Manual Upgrade

If you cannot access the AP's menu, you can put the AP into 'TFTP' mode by holding the FACTORY RESET button whilst turning the unit on and then use the Firmware Utility. That will enable TFTP mode. TFTP mode is indicated by all LEDs flashing. This mode will also be automatically enabled by the router if there is a firmware/settings abnormality. Upgrading from the web interface is easier.

---

Firmware Version	5.0.1 (Formal Release)
Release Type	<b>Regular</b> – Upgrade recommended when convenient
Release Date	06 <sup>th</sup> August 2024
Build Date	21 <sup>st</sup> May 2024
Web Version	r3564.d02d6b04
Core Version	r606
Applicable Models	VigorAP 1062c
Locale	UK Only

### **New Features**

1. Support for scheduled LED on/off and system reboot functionality

### **Improvements**

1. Password mechanism changed to force admin to change the password from the default password
2. Improvements to the wireless performance with the SSID tag
3. The TR-069 username and password settings did to allow some special characters, such as '\*' or '!'

### **Known Issues**

(None)

Firmware Version	1.5.3 (Formal Release)
Release Type	<b>Initial Release</b>
Release Date	13 <sup>th</sup> March 2024
Build Date	19 <sup>th</sup> January 2024
Web Version	r3402.0eff8ccd
Core Version	r586
Applicable Models	VigorAP 1062c
Locale	UK Only

**First Firmware Release for this model**

**Known Issues**

(None)

**[END OF FILE]**